charge any additional fee required for the extension, and credit any overpayment, to Deposit Account 06-1205.

In response to the final office Action dated July 31, 2001, the Examiner is respectfully requested to consider and enter the following amendments:

## **IN THE CLAIMS:**

Please amend Claims 4, 9, and 12 to read as follows. A marked-up copy of Claims 4, 9, and 12, showing the changes made thereto, is included in the attached Appendix. For the Examiner's convenience, all of the pending claims are presented below, regardless of whether the claim is currently being amended.

4. (Twice Amended) A cladding assembly comprising:

a plurality of building materials each of which comprises a substrate and a solar cell unit fixed to the substrate, each of the plurality of building materials fixed on a backing material by a fixing member; and

electrical conductive leads arranged between the building materials and the backing material to contact the backing material, for leading output from the solar cell units to the outside,

wherein a jacket material of each of the electrical conductive leads is composed of at least one selected from the group consisting of polyethylene resins, polyamide resins, vinylidene fluoride resins, chloroprene rubber, ethylene-propylene rubber, silicone resins, and flouroresins; and the backing material contains any one of asphalt resins, vinyl chloride resins, polystyrene resins, and polyurethane resins, and

sultant

wherein the substrate is composed of at least one selected from the

group consisting of metals, resins and glass.

- 6. A cladding assembly according to Claim 4, further comprising a connector provided at the end of each of the electrical conductive leads and composed of at least one selected from the group consisting of polyethylene resins, polyamide resins, vinylidene fluoride resins, chloroprene rubber, ethylene-propylene rubber, silicone resins, and fluororesins.
- 7. A cladding assembly according to Claim 4, further comprising a spacer member provided between the building materials and the backing material.
- 8. A cladding assembly according to Claim 4, wherein the plurality of building materials are arranged on the backing material so that the adjacent building materials are electrically connected by the electrical conductive leads.

9. (Twice Amended) A method of installing a building material comprising the steps of:

fixing a plurality of building materials each comprising a substrate and a solar cell unit fixed to the substrate on a backing material by a fixing member; and arranging an electrical conductive lead between the corresponding building material and the backing material to bring the electrical conductive lead into contact with the backing material, for leading output from each of the solar cell units to the outside;

Aud 2 rit

of at least one selected from the group consisting of polyethylene resins, polyamide resins, vinylidene fluoride resins, chloroprene rubber, ethylene-propylene rubber, silicone resins, and

flouroresins, and the backing material contains any one of asphalt resins, vinyl chloride resins,

wherein a jacket material of the electrical conductive lead is composed

polystyrene resins, and polyurethane resins, and

wherein the substrate is composed of at least one selected from the group consisting of metals, resins, and glass.

- 10. A method of installing a building material according to Claim 9, further comprising providing a spacer member between the building materials and the backing material.
- 11. A method of installing a building material according to Claim 9, further comprising arranging the plurality of the building materials on the backing material, and electrically connecting the electrical conductive leads of the adjacent building materials.

Suly)

12. (Twice Amended) An air flowing apparatus comprising:

a building material which comprises a substrate and a solar cell unit fixed to the substrate and which is fixed to a backing material with a space therebetween so that outside air flows in the space, passes through the space and is entrapped in a house or discharged to the outdoors; and

an electrical conductive lead arranged between the building material and the backing material to contact the backing material, for leading output from the solar cell unit to the outside,